

## PREPARATORY SURVEYS AT MAINDY PARK

1. It is anticipated that the survey/testing required will commence from October 2023, and that any signage or fencing required to maintain the health and Safety of users of trust land will be in place prior to the inspections being undertaken.
2. All areas of ground disturbance will be made good following completion of the survey.
3. GLL will be advised in advance of any survey work being undertaken, so users of the Velodrome can be informed, if required.
4. The following is the list of surveys which will need to be carried out:
  - a) Geotechnical Survey – This investigation will include use of a drilling rig to take soil samples at the required depth. All sample holes will be refilled.
  - b) Infiltration Testing measures absorption rate and will involve excavation pits, which will be filled in following completion of the testing.
  - c) Ground Penetrating Radar survey – non-invasive
  - d) Unexploded Ordinance Survey – this may involve ground disturbance which will be refilled on completion.
  - e) Ecological – Non-invasive
  - f) Arboriculture – Non-invasive
  - g) Invasive species – Non-invasive
  - h) Foul Drainage Survey – This will involve inspection of manholes on site
  - i) Acoustic – Non-invasive
  - j) Asbestos – This will involve samples taken of the velodrome structure to determine if asbestos containing materials were used in its construction. Any sample points will be made good and will not affect the condition of the Velodrome surface.